

## Basement Finishing Work Order

July 5<sup>th</sup>, 2024



Richard & Macy Stapler

429 N 20 E  
Vineyard, UT 84059



### DEMOLITION / PREPARATION

- ✓ Remove all temporary blanket insulation from exterior concrete walls in areas to be finished.



### CONCRETE



### FRAMING

- ✓ Frame 2x4 walls, 16" on-center layout with treated floor-plates.
- ✓ Install LVL headers for new doors and openings in bearing walls.
- ✓ Install fire-blocking and draft-stop around perimeter walls - as required by code.
- ✓ Construct fur-downs around duct work in finished areas.

#### **Playroom:**

- ✓ Frame a short door way for the playroom's Dutch-door.
- ✓ Frame in a door opening in the stairway wall for a play area under the stairs.
- ✓ Frame a window opening in the playroom wall.



### HEATING, VENTILATION AND AIR CONDITIONING (HVAC)

- ✓ Add 5 new heating-tube runs and registers to the existing furnace system.
- ✓ Install up to 2 cold-air returns (as needed for proper volume) at floor level for better function.
- ✓ Install a bathroom exhaust fan with a 5" exhaust tube and exterior cover.
- ✓ Inspect the HVAC system for breaches/openings prior to blow-in ceiling insulation.



### PLUMBING

#### **Bathroom:**

- ✓ Plumb the supply lines and drain for the sink, tub/shower and toilet.
- ✓ Provide and install a BootzCast, standard-size, steel, ceramic-coated, insulated tub (60" x 30" x 14").
- ✓ Provide and install a brushed-nickel, Moen-Brantford, 4" center-set, lave faucet.
- ✓ Provide and install a brushed-nickel, Moen-Brantford shower faucet.
- ✓ Provide and install a Viper toilet (your choice of round or elongated bowl).



### ELECTRICAL

#### **General:**

- ✓ Wire to code and install typical circuit breakers (when applicable), including GFCIs for the bathroom and mechanical room.
- ✓ Install 20 plugs, 13 switches, 3 CAT5e/RG6 lines, 3 smoke detectors, 11 3000K LED can/disc-lights and 6 light fixtures.

⚠ An additional circuit breaker panel is not included.

#### **Entertainment:**

- ✓ Install 1 cable-management chase-tube for a wall-mounted TV location in the family room (components below the TV).



### INSULATION

#### **Wall Insulation:**

- ✓ Insulate with R-19 fiberglass batts on all exterior walls in finished areas.
- ✓ Insulate the interior walls of the mechanical room and bathroom.


#### **Ceiling Insulation:**

- ✓ Install the superior 1lb density, cellulose blow-in in the ceiling of rooms to be finished.



### DRYWALL

- ✓ Install ½" drywall on all surfaces to be finished with bull-nose corners and hand-textured ceilings.
- ✓ Finish the walls to closely match the texture upstairs: Old-World.
- ✓ Finish the stairway and finish under the stairs.
- ✓ Install DensShield around the shower.



### **FINISH CARPENTRY**

#### **Doors:**

- ✓ Install double, ball-catch or magnet-catch doors on applicably-sized closets.
- ✓ Install a solid-core door on the mechanical room and a weather-tight door on the storage room.
- ✓ Install a Dutch-door on the play area.

#### **Trims:**

- ✓ Install wood window-sills with an apron molding below the windows.
- ✓ Install painted skirt-boards along the edges of the stairs.

#### **Shelving:**

- ✓ Install multiple wooden, built-in shelves and an organizer stack in bedroom closets.

#### **Playroom:**

- ✓ Install a gable with shingles above the playroom Dutch-door.
- ✓ Install a window frame in the playroom window opening.



### **PAINT**

#### **Paint:**

- ✓ Paint a single-color finish in all non-utility rooms (includes all necessary prep, primer and 2 separate finish coats).
- ✓ Paint the existing stairway hand-rail.



### **TUB/SHOWER SURROUND**

#### **Tub/Shower Combo:**

- ✓ Install a custom-fit, cultured-marble tub surround (3-slabs, approx. 60" tall, 3/8" thick.)
- ✓ Includes installation of two items: either 2 shampoo-shelves or 1 soap-dish and 1 shampoo-shelf.



### **CABINETS**

- ⚠ Cabinetry in this bid is White Shaker.

#### **Bathroom:**

- ✓ Provide and install a 42" cabinet (with 2 doors and 2 drawers).



### **COUNTERTOPS**

#### **Bathroom:**

- ✓ Install a 3cm granite remnant countertop including a 4" backsplash.
- ✓ Includes a polished-edge for an under-mount sink.
- ✓ Provide and install a white, oval, under-mount sink.



### **FLOORING**

#### **Family room, Bedroom, Playroom, hallway, up the stairs, under the stairs:**

- ✓ Install carpet.

#### **Bathroom:**

- ✓ Install tile flooring.



### **HARDWARE/ACCESSORIES**

- 📌 FYI: Homeowner to provide and install own mirror.
- ✓ Install a bathroom accessory set. (One towel bar, one towel ring and one TP holder).
- ✓ Install door knobs and stops that are as similar to your upstairs as available from our suppliers.
- ✓ Install 3 closet rods.
- ✓ Install an escape ladder in each bedroom window well where required. (1)



#### ITEMS NOT INCLUDED AND MISC NOTES

Items not included unless specifically noted:

⚠ Prevention from (or repair of) external water leakage.	⚠ Moving or redoing underground plumbing.
⚠ Correcting any unforeseen, previously done, faulty work.	⚠ Sub-grade camera work. (Price starts at \$250.)
⚠ Altering or moving of bearing walls.	⚠ Installing, moving or discarding of any appliance.
⚠ Repairing, adjusting or replacing of any security items.	⚠ Installing or mounting TVs, projectors or A/V devices.
⚠ Running (or connecting to) upstairs low-voltage lines.	⚠ Altering (or adding to) the existing heating trunk system.
⚠ Collection panel(s) or data/voice hardware.	⚠ Adding or altering zoning equipment.

Notes:

- ❗ All sub-grade plumbing and concrete work associated with the bid are estimates based on normal/anticipated conditions.
- ❗ Tub and toilet drains must be in exact positions for the bathroom layout to work as designed. Costs (above anticipated estimates) for concrete cutting, patching, jackhammering, digging (or abnormal procedures) are extra.
- ❗ Closets, storage areas, under stairs and other utility areas are painted one color only (usually the trim color).
- ❗ Circuit breakers, switches, receptacles, boxes, wire sizes, etc. are industry standard and not brand-specific.
- ❗ We will replicate the termination-ends of our low-voltage lines to that of the existing low-voltages lines.
- ❗ Drywall price assumes that drywall can be stocked by the typical removal and re-installation of a basement window.
- ❗ Actual floor covering material needed may vary slightly between sketch estimates and actual field measurements.
- ❗ For LVT/LVP flooring, additional costs for extra prep/floating, etc. may be necessary for uneven concrete floors.
- ❗ Our insulation, as bid, meets or exceeds the requirements being enforced for basement finishing in most cities.
- ❗ Any item or process required by the city inspector that is not included in the bid will be added to your bill.